HERCULES INDSUTRIAL PCA 1256676 Revision C

Revision	NOTES	Engineer	DATE
Α	Document creation	BAP	2023-10-24
В	 Update board revision check section Update Modem section IMU section updated 	ВАР	2023-11-20
С	 Update Wifi Section Reordered so that Wifi is before the modem	BAP	2023-12-18

This document is intended as a continuation of the Functional Test Procedure for PCA 1256673. Please refer to the Setup and Test Sequence in that document first.

Note: Either the Accelerometer or the IMU will be installed, not both.

Board Revision Check:

- 1. Execute the command "version"
- 2. The version command should read TELEM_REV_BITO through TELEM_REV_BIT3, BOARD REVISION BIT 0 through BOARD REVISION BIT 3, machine app version and bootloader version. The Telemetry board revision shall match the revision number listed in the released drawing of 1256676.

IMU Check:

- 1. Run command "imu?"
- 2. The response shall include the following: IMU successfully initialized() = True:1

Wifi Modem Check:

- Run command "wifi e"
- 2. Run command "wifi ?"
- 3. The response shall include the following: "Wifi operational state: up".

Cellular Modem Check:

- 1. Run command "telemetry ?"
- 2. The response shall include status of both UART and USB:

Communication Protocol	Passing Response
UART	"OK" or "RDY" or "APP RDY"
USB	"OK" or "RDY" or "APP RDY"

END OF TEST.